BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT36931

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/06/2019-20, Date: 15.06.2019

Drilling of Borewells providing pump, motors and laying pipeline at Agrahara layout, surrounding area in ward no. 05 Byatarayanapura sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K R Santhosh Kumar ( )		
				In Figures		In Words
1	4	Geophysical investigation of site for sinking borewell for supplying drinking water to the habitation either through the hand pump, MWS or P.W.S.S. by vertical electrical sounding by adopting venner or schlumbergers's method, including reconnaissance survey of geological formation, Geological investigation of existing ground water in vicinity, its quality, quantity & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 mtr in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site, engaging technical personal and labour required etc (P.NO-47, I.NO-9.4, PRED 12-13 SR)	Each	2016.0	8064.00	Rupees Two Thousand Sixteen Only
2	200	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) (P.NO-47, I.NO-9.1, PRED 12-13 SR) 0 to 50 m	Rmtr	327.79	65558.00	Rupees Three Hundred Twenty Seven and Seventy Nine Paise Only
3	200	50 to 100 m	Rmtr	428.48	85696.00	Rupees Four Hundred Twenty Eight and Forty Eight Paise Only
4	200	100 to 150 m	Rmtr	476.68	95336.00	Rupees Four Hundred Seventy Six and Sixty Eight Paise Only
5	200	150 to 200 m	Rmtr	503.46	100692.00	Rupees Five Hundred Three and Forty Six Paise Only
6	200	200 to 250 m	Rmtr	582.73	116546.00	Rupees Five Hundred Eighty Two and Seventy Three Paise Only
7	200	250 to 300 m	Rmtr	624.51	124902.00	Rupees Six Hundred Twenty Four and Fifty One Paise Only
8	280	300 to 370 m	Rmtr	646.88	181126.40	Rupees Six Hundred Forty Six and Eighty Eight Paise Only
9	256	Supplying of ISI Mark 175 mm nominal bore medium black ERW casing pipe of 5mm thick black electric resistance continous welded midle steel tube material confirming to IS 1387/1993 and manufactured from hot rolled steel skelp/stripes in random length of 4 to 7 mtr both ends threaded confirming to IS 554/1985 one end(including of all taxes) (P.NO-III, I.NO-84, PRED 12-13 SR)	Rmtr	1419.34	363351.04	Rupees One Thousand Four Hundred Nineteen and Thirty Four Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K R Santhosh Kumar ( )		
				In Figures		In Words
10	40	Providing and fixing 250mm dia PVC pipe and as per specification and directions. (BWSSB SR 13-14, P.No.53 I.no.1 of sl.no.11.)	Rmtr	1178.32	47132.80	Rupees One Thousand One Hundred Seventy Eight and Thirty Two Paise Only
11	4	175 mm dia M.S. Casing cap (P.NO-III, I.NO-85, PRED 12-13 SR)	Each	107.12	428.48	Rupees One Hundred Seven and Twelve Paise Only
12	36	M.S. Casing pipe collars 'C' Class (P.NO-III, I.NO-86, PRED 12-13 SR)	Each	160.68	5784.48	Rupees One Hundred Sixty and Sixty Eight Paise Only
13	88000	Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc,. complete box of 21600 sq cm (P.NO-530, I.NO-39 b, BWSSB SR 13-14)	Sqm	0.35	30800.00	and Thirty Five Paise Only
14	180	Labour charges for erection of new /repaired submersible pumpset along with GI pipes (32/50mm) cable (new submersible pumpset if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (each length = 6.00m) (P.No - 564, I.No - 3, BWSSB SR 13-14)	No	94.27	16968.60	Rupees Ninety Four and Twenty Seven Paise Only
15	4	Erection of combined panel board meter board with all necessary materials and labour including providing CC 1:3:6 foundation bed etc,. Complete for basement out door type. (MR)	No	494.0	1976.00	Rupees Four Hundred Ninety Four Only
16	12	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... P No. 32/I No 3b KPWD Electrical SR 2010-11	No	156.0	1872.00	Rupees One Hundred Fifty Six Only
17	140	Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable (confirming to IS 1554) (P.NO - 553, I.NO - 10 (d), BWSSB SR 13-14)	Mtr	176.75	24745.00	Rupees One Hundred Seventy Six and Seventy Five Paise Only
18	140	Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc,. Complete sutting road surfaces (P.NO - 554, I.NO - 12 (b), BWSSB SR 13-14)	Mtr	58.92	8248.80	Rupees Fifty Eight and Ninety Two Paise Only
19	12	Supplying and fixing Class-A GI Pipe on pole/ wall/drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm (P.NO - 555, I.NO - 15 (b), BWSSB SR 13-14)	Mtr	306.36	3676.32	Rupees Three Hundred Six and Thirty Six Paise Only
20	4	Supplying and fixing wiring earth electrode for grounding conduits, IC cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit,/ the pit should be filled with equal proportion of salt and charocal 150 mm alround the pipe to complete depth the connections from the pipe to the conduit etc,. is to be established though GI wire of size as per ISI specification 7.3.3 of ISI 732 using 12mm dia boalts, nuts washers and checknuts etc,. the pipe shall have 16 through holes of 122mm dia (P.NO - 552, I.NO - 7 , BWSSB SR 13-14)	No	1767.48	7069.92	Rupees One Thousand Seven Hundred Sixty Seven and Forty Eight Paise Only
21	4	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmmUG cable filled with necessary bitumen/ insulating compound complete with terminals, clamps, bolts nuts and washers etc, (P.NO - 555, I.NO - 16 (b) , BWSSB SR 13-14)	No	282.8	1131.20	Rupees Two Hundred Eighty Two and Eighty Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K R Santhosh Kumar ( )		
				In Figures		In Words
22	4	Supplying and fixing of polished wood board made of not less than 15mm thick plank on both sides with planks made out on not more than 2 pieces and fixing the same to wall using tapered inverted wooden plugs screws etc., Size 20 x 20 x 2.5 inches (P.NO - 521, I.NO - 2 (f), BWSSB SR 13-14)	No	324.04	1296.16	Rupees Three Hundred Twenty Four and Four Paise Only
23	4	Borewell Cap and Clamp Set (PWD SR 2018-19, Page No. XLVII, Sl nO. 17)	Set	1872.0	7488.00	Rupees One Thousand Eight Hundred Seventy Two Only
24	2	Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings 17.50 HP 30 stage (P.NO-XXXXIII, I.NO-34, PWD SR 18-19)	No	75011.04	150022.08	Rupees Seventy Five Thousand Eleven and Four Paise Only
25	2	20 HP 40 Stage	No	94218.8	188437.60	Rupees Ninety Four Thousand Two Hundred Eighteen and Eighty Paise Only
26	1340	Providing, laying & jointing GI pipes confirming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc,. complete 'A' grade(excluding cost of fittings) 50mm dia GI pipe B Class (SR 18-19 PWD, P.No.XLVII Sl.no. 1	Rmtr	431.6	578344.00	Rupees Four Hundred Thirty One and Sixty Paise Only
27	224	Supply and fixing Collar for GI Pipes 50MM (Page No. XLVII, Sl NO.2, PWD SR-2018-19	No	187.2	41932.80	Rupees One Hundred Eighty Seven and Twenty Paise Only
28	2920	Supplying of submersible pump cable 1X3X6..0 Sq.mm (Page No. XLVII, Sl NO. 8, PWD SR-2018-19	Mtr	149.76	437299.20	Rupees One Hundred Forty Nine and Seventy Six Paise Only
29	4	Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc,. completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above Up to 20HP with star delta starter (MR) Page No. XLVII, Sl NO. 13, PWD SR 2018-19	No	21840.0	87360.00	Rupees Twenty One Thousand Eight Hundred Forty Only
30	4	Supplying & delivery of brand 50mm Gate Valve. (PWD SR 18-19, P.NO.XLVII Sl.no, 15	No	1872.0	7488.00	Rupees One Thousand Eight Hundred Seventy Two Only
31	11	Supplying & delivery of brand 50mm Non Return Valve. (PWD SR 18-19, P.NO.XLVII Sl.no, 16	No	1872.0	20592.00	Rupees One Thousand Eight Hundred Seventy Two Only

Signature of the contractor

6/09

Executive Engineer

6/09

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K R Santhosh Kumar ( )		
				In Figures		In Words
32		Supplying and fixing MCB (P.NO - XLVII, SL.NO - 19, PWD SR 18-19)	No	936.0	3744.00	Rupees Nine Hundred Thirty Six Only
33	10	GI Pipe 40mm A Class, for Electrical Pole (P.NO - XLVII, SL.NO - 20, PWD SR 18-19)	Mtrs	416.0	4160.00	Rupees Four Hundred Sixteen Only
34	4	Pot Head (P.NO - XLVII, SL.NO - 21, PWD SR 18-19)	No	374.4	1497.60	Rupees Three Hundred Seventy Four and Forty Paise Only
35	705.6	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications (P.NO - 6, I.NO - 2.3, PWD SR 18-19)	Cum	329.62	232579.87	Rupees Three Hundred Twenty Nine and Sixty Two Paise Only
36	1568	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete (P.NO - 94, I.NO - 13.73.2, PWD SR 18-19)	Mtr	410.09	643021.12	Rupees Four Hundred Ten and Nine Paise Only
37	705.6	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications (P.NO - 7, I.NO - 2.11, PWD SR 18-19)	Cum	133.39	94119.98	Rupees One Hundred Thirty Three and Thirty Nine Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92